

**SCHEDULES OF WORK****Name of work:**

Renovation of Link Corridor from Gyane OPD to Gyane waiting shed, RIMS, Imphal.

**Estimated cost :Rs. 4,64,281/-****Time allowed:****1 Month**

Sl.no.	Items of works	Qty	Unit	Rate quoted	
				Rate in figure (Rs)	Rate in words
1	Providing and laying cement concrete in foundation and plinth excluding the cost of centering and shuttering 1:2:4 (1 cement :2 coarse sand :4 graded stone aggregate 20 mm nominal size)	1.70	cum		
2	Providing wood work in trusses, purlins, rafter, posts, post plate& the like wrought frame hoisted & fixed in position ( c ) Uchan/Tairen/Tolhao	9.37	cum		
3	Providing & fixing 20 mm plank as eave board with (a) Uningthou wood	27.77	cum		
4	Corrugated G.I. sheet 24 B.G.fixed with galvanised iron J or L hooks 8 mm dia G.I. limpet & bitumen washer complete, excluding the cost of purlins, rafters & trusses	208.21	sqm		
5	Ridges or hips 610 mm over all in plain G.I. sheet 24 B.G. fixed with galvanised iron J or L hooks 8 mm dia G.I. Limpet & bitumen washers complete.	52.90	Rm		
6	Applying ready mixed priming coat pink primer of approved quality on wood work.	283.90	sqm		
7	Painting ( two or more coats ) with superior glass enamel paint of any shade of approved quality on new work to give an even shade.	263.90	sqm		
8	Painting ( one or more coats ) with Black Japan to give an even shade.	189.57	sqm		