



क्षेत्रीय आयुर्विज्ञान संस्थान, इंपाल: मणिपुर
REGIONAL INSTITUTE OF MEDICAL SCIENCES, IMPHAL, MANIPUR
(स्वास्थ्य और परिवार कल्याण मंत्रालय, भारत सरकार के अंतर्गत एक स्वायत्त संस्थान)
(An Autonomous Institute under the Ministry of Health & Family Welfare, Govt. of India)

Phone : 0385-2414720
0385-2414750
e-mail : rims@rims.edu.in
website : www.rims.edu.in

CORRIGENDUM

No.Pur/Equi/Coll(Medi)/1/2025-Pur-Sec: In partial modification of this Institute's GeM Tender No. GEM/2025/B/6177332 dated 28-04-2025 for supply, installation, testing & commissioning of Digital Subtraction Angiography Unit (Single Plane) on Turnkey Basis, for the Department of Medicine, RIMS, Imphal, the technical specification for the Civil works have been modified and enclosed as "Annexure-A". The rest of the contents of the Tender specification remains unchanged.

2. This issues with the approval of the Director, RIMS, Imphal.

Signed by

Mecolt Rajkumar Singh

Date: 04-06-2025 17:11:56

(R.K. Mecolt Singh)
Deputy Director (Admn.)

Copy to:-

1. P.S. to Director, RIMS, Imphal - for his kind infomation.
2. Medical Superintendent, RIMSH, Imphal.
3. The HoD, Deptt of Medicine, RIMS, Imphal.
4. Executive Engineer (Civil), RIMS, Imphal.
5. System Administrator - for uploading the Corrigendum in the RIMS, Website.
6. Section Officer (Purchase), RIMS, Imphal.

Annexure A

As per approved technical specification of MoHFW	Amended Specification
<p>8. Civil work :</p> <ul style="list-style-type: none"> • Civil construction work including construction of brick wall if any, plastering, flooring as per the approved plan and equipment layout plan. • Concrete bed at DSA equipment area. • Platform for unloading and shifting the DSA should be provided if necessary. • Cable tray, trench & channel - necessary trenches, cable tray and channels at required location would be provided. • All the construction work to be done as per the final plan approved by the Consignee. <p>A. Flooring</p> <ul style="list-style-type: none"> • 600 x 600 mm vitrified tiles vitrified tiles 100mm tile skirting to match in the entire DSA complex apart from the DSA Exam room, equipment room and UPS room. • 50 mm thick cement concrete flooring with Vinyl flooring in DSA Exam room, equipment / UPS room. <p>B. Painting.</p> <ul style="list-style-type: none"> • Two coats Plastic Emulsion Paint over 2 coats of wall putty including primer in patient pre Baration area, Lobby area, console room, & Equipment room etc. • Full height wall tiles should be provided in the DSA room. <p>C. False Ceiling</p> <ul style="list-style-type: none"> • Acoustical tile for ceiling with light weight insulating material of high quality supported on grid or finished seamless with support above ceiling, Finished with white paint or powder coated with white paint, if metallic. • Ceiling height to suit the equipment mount and clearances. <p>D. Plumbing work</p> <ul style="list-style-type: none"> • All water pipes and fittings (for Scrub etc) shall be of high density polythene of approved and standard make. The gratings shall be brass chrome plated. All plumbing accessories should be of standard make. 	<p>8. Civil work :</p> <ul style="list-style-type: none"> • Platform for unloading and shifting the DSA should be provided if necessary. • Cable tray, trench & channel - necessary trenches, cable tray and channels at required location would be provided. • All the construction work to be done as per the final plan approved by the Consignee. <p>A. Flooring</p> <ul style="list-style-type: none"> • 50 mm thick cement concrete flooring with Vinyl flooring in DSA Exam room, equipment / UPS room. <p>B. Painting.</p> <ul style="list-style-type: none"> • Full height wall tiles should be provided in the DSA room. <p>C. False Ceiling</p> <ul style="list-style-type: none"> • Acoustical tile for ceiling with light weight insulating material of high quality supported on grid or finished seamless with support above ceiling, Finished with white paint or powder coated with white paint, if metallic. • Ceiling height to suit the equipment mount and clearances. <p>D. Plumbing work</p> <ul style="list-style-type: none"> • All water pipes and fittings (for Scrub etc) shall be of high density polythene of approved and standard make. The gratings shall be brass chrome plated. All plumbing accessories should be of standard make.